



Whipple Consulting Engineers, Inc.

WCE No. 2013-1166

July 23, 2015

Revised October 13, 2016

City of Spokane Valley
11707 E Sprague Ave, Suite 106
Spokane Valley, WA 99206

Attn: Mr. Gabe Gallinger, P.E.

Re: Painted Hills Flood Control Development Narrative (Storage Area #1 & #6, SA1)

Dear Gabe:

This letter is intended to present the flood control plan for the above referenced storage areas in anticipation of the future development.

Background

A hydrologic and hydraulic analysis for Chester Creek was completed by Michael Baker Jr., Inc. and approved by Spokane County in a letter to the Federal Emergency Management Agency dated August 6, 1990. There are no long-term gage records for Chester Creek. The limited gage measurements on Chester Creek were collected near the Dishman-Mica Road crossing of Chester Creek for December 1994 through March 1995 and November 1995 through February 1996 when no flood events occurred. In February 2006, the hydraulic analysis for Chester Creek was revised by West Consultants, Inc. under a FEMA contract. The analysis established flood magnitude-frequency estimates for the watercourse. A steady flow model has been developed for Chester Creek.¹

The reports conclude that spring floods in the upper Spokane River basin are due to snowmelt runoff from high elevation watersheds. Such floods are of less significance on Chester Creek because the lower elevation of the water shed limit the size of the snowpack so spring runoff occurs about a month earlier and the more gradual rates than on the Spokane River. Nearly all maximum annual flood peaks on Chester Creek occur during the winter. Warm winds and rain can melt the snow rapidly. When winter rain causes snowmelt on frozen soil conditions, short-duration, intense runoff generates a flood peak during winter storms. During the more extreme events, Chester Creek runs over its banks filling depressions in the flood zone.¹

The duration of flooding is generally between 100 hours and 1000 hours, or between four days and forty days with smaller events occurring with greater frequency than large events.¹

Channel geometry for Chester Creek were developed from surveys conducted in March 2003. Overbank geometry was developed from topography developed by TerraPoint (2003). Flood plain boundaries for Chester Creek and Unnamed Tributary to Chester Creek were delineated using 2 foot contour interval maps developed by TerraPoint from LiDAR data. ¹

Previously, a watershed plan for Chester Creek was designed with management recommendations for drainage, flooding, water quality, and riparian habitat. As a result, flood control improvements have been implemented along Chester Creek. The improvements area began at the Painted Hills Golf Course. In 1998, a project to install new culverts and extensive dredging of the channel between Thorpe Road and Schaffer Road was implemented. Two large volume borrow pits were constructed downstream. Each pit was designed for the retention and infiltration of Chester Creek floodwaters up to a 25 year event. One borrow pit was constructed just north of E 40th Avenue and the other just south of 28th Avenue. ¹

Before the storage areas #1 and #6 are to be modified (see Site Element Plan), it is important to understand where they are within the Chester Creek Basin, and what floodwaters they receive. Within the Chester Creek Basin, the storage areas are generally located in the northeast corner of the basin along the edge of the valley floor. Specifically, north of Thorpe Road (Storage Area 1) and to the east of 40th Avenue (Storage Area 6).

The flood condition flows as identified by West Consultants are separated into three parts in relation to the three directions of flow that enters into the Painted Hills Development: the main flow (Golf Course Overflow Reach) across Thorpe Road, the secondary (Unnamed Tributary) flow from Highway 27, and the secondary flow across Madison Road. The project is proposing to redirect the anticipated flows of the identified flood events for storage area #1 (main flow and secondary flow) to a discharge point at the north end of the development and for storage area #6 (Unnamed Tributary) to an offsite discharge point to the east of the development.

Storage Area #1 is a large storage area that encompasses the majority of the former Painted Hills Golf Course as well as areas to the east of Madison Road. There is no outflow route for this storage area so it is classified as compensatory storage and is allowed to infiltrate through the native soils and into the Spokane Rathdrum Aquifer. The soils below the storage area include the Spokane Rathdrum Aquifer as its base followed by layers of coarse sands that are topped by soils of an alluvial fan or an area of natural deposit from Chester Creek, before the creek was channelized.

The floodwaters that enter Storage Area #1 are identified on the July 6, 2010 Firm Map as the Chester Creek Golf Course Overflow. The Chester Creek Golf Course Overflow originates at a point to the south of Thorpe Road where there was at one time a breach in the man-made channel of Chester Creek. The breach was reportedly from a lack of maintenance and the overgrowth of vegetation in the main channel that blocked the main channel during a storm event. This flow of floodwater enters the storage area from the south at a low point in Thorpe Road through two 10" culverts and, if flow is larger, by overtopping the road.

Storage Area #6 is a smaller storage area that is located east of 40th Avenue primarily within a 30-foot-deep gravel pit that was excavated during the early development years of Spokane Valley. Spokane County obtained a drainage easement over the pit in 1983 for storm drainage purposes. The overflow route of storage area #6 is along the south side of 40th Avenue and flows into Storage Area #1 via

culverts under Madison Road. The soils below the storage area include the Spokane Rathdrum Aquifer as its base followed by layers of coarse sands and gravels that were further exposed by the gravel pit excavation.

The Main Flow Across Thorpe Road

Concept Design and Process

For the concept design the 100-year event was used to size facilities. The initial design was to capture the approximately 1,594,812 cf or 36.61 ac-ft into a deep pond for storage and discharge through evaporation. However, it occurred to us when reviewing the Geotechnical Evaluations, Phase I (December 31, 2013 – Revised August 29, 2016) and Phase II (July 23, 2015) that there are “valley gravels” or well-draining soils that lead directly to the Spokane-Rathdrum Aquifer under the poor draining soils that cover the site. If we connected into these soils the compensatory storage may be treated and discharged into these soils. Initially we were looking at 128 double depth drywells with a design outflow rate of 1.0 cfs each. That would provide twice the outflow rate of 128 cfs to the 64 cfs peak inflow rate of the flow across Thorpe Road. However, as the construction consideration of the drywells was made, it was decided that a gravel gallery system sized to the storm would more evenly distribute the stormwater across a larger area. But after further geotechnical investigation, it was determined the south area may have groundwater at or above the proposed depth of the gravel galleries. Therefore, a new site for the gravel galleries was chosen at the north end of the development where groundwater was determined to be much deeper than the galleries. See Supplemental Geotechnical Evaluation by IPEC dated April 19, 2016.

Proposed Design

See Site Element Plan in the attachments.

Box Culvert/Open Channel

The flow coming from the breach of the east levee upstream on Chester Creek is anticipated to approach Thorpe Road as before at the low point where there are currently 2-10” culverts within the natural drainage way or Golf Course Overflow Reach. The flow will then enter into a 30 foot wide by 3 foot high box culvert under Thorpe Road, replacing the 2 existing culverts. The roadside ditches along Thorpe Road will be regraded to ensure positive flow toward the box culvert. Given the topography of the area, aside from shallow puddles, all stormwater will enter into the proposed box culvert. On the north side of Thorpe Road the flow will exit the box culvert and enter into a 5 foot wide concrete open channel that flows to the east.

Pipe Mainline

The open channel will then turn north and transition into a buried pipe system with manholes along the west side of Madison Road. The flow will enter into a 48” floodwater pipe at the headwall and continue for approximately 270 feet and then transition into a 60” floodwater pipe to the north end of the project with an outfall into a bio-infiltration channel. Each manhole along Madison Road will have a sump for the settling of particles in low flow conditions. These particles or silt can then be vactored out of the manholes as part of the routine maintenance.

Bio-infiltration Channel

The bio-infiltration channel receives the stormwater from the 60" pipe and will be planted with tall dryland grasses. The flow of the floodwater overland through the tall grass provides the last phase of cleaning before the floodwater flows into the gravel gallery system for ultimate disposal into the aquifer, its final destination. See Bio-infiltration worksheet in the attachments.

Gravel Gallery System

Floodwater from the downstream end of the bio-infiltration channel is piped via two 36" pipes to manholes at the east end of the gravel gallery system. From the manholes the floodwater is piped to drywells to evenly distribute the floodwater and enters the gravel galleries by either flowing through the drywell barrels or distributing through 24" pipes to the next drywell and through pipe cross fittings.

The gravel gallery system is based upon four 10 foot wide by 13 foot deep by 450 foot long infiltration trenches that are lined with geo-fabric per WSDOT Std. Spec. 9-33.2(1) and filled with gravel drywell material in conformance with WSDOT Std. Spec. 9-03.12(5). Within the top 3 feet of the infiltration trench runs a 24" pipe at a 1% slope that connects drywells located at the ends and center (totaling 12 drywells) within each trench segment. Pipe cross fittings will be installed every 50 feet with geotech fabric banded over the open ends to allow water within the pipe to enter the rock section without rock entering the pipe. The cross fittings are offset from each other across adjacent trenches. This equidistant separation allows for a balanced distribution of water within the gravel gallery system ensuring all of the gallery is filled and used for infiltration. When the next drywell fills or rises to the invert of the next pipe, stormwater will continue to the next fitting/drywell until the gravel gallery is filled. Once filled the gallery is at its maximum design infiltration rate of 118 cfs (see gravel gallery worksheet in the attachments). A 100-year storm has a peak flow rate in this system of 64 cfs so with a design outflow rate over 1.8 times greater than the design inflow rate the system will not be overwhelmed. This is a conservative measure of protection.

Infiltration Rate

The Phase I geotechnical evaluation performed laboratory grain size analysis tests on soils from the test pits, including at Test Pit TP-29 at the 10 to 12-foot depth. This test showed a fines content of 2.3 percent with design drywell rates of 0.3 and 1.0 cfs for Type A and Type B drywells, respectively.

A full-scale dry well test was performed at the north end of the site. Based on this test we used the design flow rate of 1.8×10^{-3} cfs/sf for design of the gravel galleries in the open space area north of the proposed Cottages residential area. See attached IPEC Geotechnical Report dated June 28, 2016.

Maintenance of the gravel gallery system is a semi-annual inspection of the gallery through the system drywells looking for a build-up of sediment and debris, and if needed, the removal of the sediment and debris by a vector truck.

Levee

The project site is protected from the main channel of Chester Creek by a levee on the northerly and easterly side of the creek from Thorpe Road to Dishman-Mica Road. This levee will be improved by some minor grading to increase freeboard in the area of the Thorpe Road culvert and at the existing cart crossing bridges. Additionally, new levee will be constructed from the existing levee northwesterly along the easterly side of Dishman-Mica Road terminating at Wilbur Road.

The Secondary Flow Across Madison Road:

The flow across Madison Road is divided into 5 basins from the heights above and to the east of Madison Road that correspond to the 5 culverts that are placed under Madison Road. The most northerly culvert does not have an outlet on the west side of Madison Road. Therefore, the floodwater distributes along the east side of Madison and appears to be separated into 4 culverts that cross Madison Road at Stations (S-N) 13+22, 20+44, 24+43 and 30+43. As the development proposes to widen Madison Road on the west side, the 4 culverts will be replaced and extended. Since the proposed inverts of the extended culverts will fall below the proposed grade of the roadside swales, the culverts will connect into the 60" pipe.

The storm water along the west side of Madison Road will be collected in roadside swales where it will receive treatment. The swales will have catch basins with the rim set 6" above the swale bottom. Any excess treated flow that does not infiltrate and exceeds a 6" depth will enter the catch basins. The catch basins will be connected to the 60" storm pipe.

West Consultants provided the following 100-year storm flows for each culvert during the 100-year storm. We are using these flows to size and design floodwater facilities.

STA.	100 Year Storm Flow (cfs)	
13+22	4	
20+44	1	
24+41	1	
30+42	2	
38+98	7	

Any floodwater generated west of the triangle pond along E 40th Avenue flows to the west. Then at Madison Road it flows south between the road and the easterly hillside. These flows will be intercepted with the replacement culverts installed at Stations 13+22 through 30+42 that are connected at manholes into the 60" pipe.

The Secondary Flow From Highway 27

Proposed Design

The 16 cfs flow from Highway 27 (Unnamed Tributary) is currently conveyed via a 36" culvert that empties into a ditch that flows across the Gustin property. The stormwater flows through the ditch and into the existing borrow pit within the triangular parcel located northeast of E 40th Avenue. The ditch has been maintained over the years by the property owner to ensure that whatever floodwater comes out of the culvert under Highway 27 will be conveyed to the borrow pit. With this project the ditch will be regraded to a uniform 3 foot bottom width and its southern berm will be reconstructed to be certified as a levee so that FEMA does not immediately assume that the berm is breached and the stormwater flows to the lower area to the south. The area north of the ditch is at a higher elevation that prevents flood water from going north.

Design Elements:


Proposed Pond 17,060 sf @ El: 1990.00; 35,812 sf @ El. 1995.00; 84,416 sf @ El. 2000.00
Drywell spacing 30', total drywell outflow 18.0 cfs
Maintenance Access Road: 6" gravel, max grade 10%, min. radius 35'
Fenced with gate

Infiltration Pond

WCE proposes to improve the outflow of the borrow pit by regrading and expanding the lowest bottom area of the borrow pit and installing 18 double depth drywells into the bottom of the internal pond. The drywells will provide outflow during a frozen ground condition. Each double depth drywell will provide a design outflow of 1.0 cfs for a total of 18 cfs per the recommendations in the Geotechnical Evaluation by IPEC dated October 14, 2014.

If you have any questions or comments in regard to this letter please feel free to contact us at (509) 893-2617.

Sincerely,
WHIPPLE CONSULTING ENGINEERS, INC.



Todd R. Whipple, PE

TRW/bng

CC: File

ATTACHEMENTS

Bibliography

Site Element Plan

Box Culvert/Concrete Channel Calculations

Pipe System Calculations

Gravel Gallery Worksheet – North

Bio-infiltration Channel Worksheet

Madison Rd Culvert Flows

V-Ditch Rock Calculations



IPEC Geotechnical Report dated June 28, 2016

BIBLIOGRAPHY

- 1) Dawes, Larry. August 30, 2016. Biological Evaluation, Buffer Averaging, and Habitat Management Plan for the Painted Hills PRD. Biology Soil & Water, Inc., Spokane Valley, WA. 12-13.

SITE ELEMENT PLAN

UNDERGROUND SERVICE ALERT
 ONE-CALL NUMBER
811
 CALL BEFORE YOU DIG
 CALL 800.451.7000



Spokane County Permit
 No. _____
 Elevation
 Grading
 City of Spokane Valley
 Permit No. _____
 SUB-2016-0091
 FPD-2016-XXXX
 ECR-2016-XXXX
 City of Spokane Valley
 Development Engineering
 New Street Name - Public
 Not Reviewed
 Reviewed for Conformance to
 Spokane Valley Code, Chapter 1.2
 Date Accepted _____
 Authorizing Commission



SEPTEMBER 2016
 PLANS
 NOT APPROVED
 BY AGENCY

SHEET
C1-3
 JOB NUMBER
13-1166

SPokane Valley Painted Hills PRD
SITE ELEMENT PLAN
DISHMAN-MICA RD.
SPokane Valley, WA



DATE	BY
DESIGNED	JPP
CHECKED	JPP
IN CHARGE	JPP
OTHER	



PROJ #:
 DATE: 08/17/16
 DRAWN: JPP
 REVIEWED: TWW

SCALE:
 HORIZONTAL: 1" = 200'
 VERTICAL: N/A

DATE	BY
DESIGNED	JPP
CHECKED	JPP
IN CHARGE	JPP
OTHER	

DATUM: NAVD - 88
 THIS IS A PRELIMINARY PLAN FOR THE SOUTH PRONGERIA SUBMITTAL PROJECT
 WITH AN ELEVATION OF 2000 AT PRANTON - 2008/07
 THIS DRAWING WAS USED FOR THE VERTICAL ENGINEERING FOR THIS
 MAP








NOT TO SCALE

GEO TECH EVALUATION SITES
 TP = TEST PIT
 TH B = TEST HOLE BORE

2 EXISTING 10" CULVERTS
 THORPE RD BOX CULVERT
 30"W X3'H BOX CULVERT
 CHESTER CR. BOX CULVERT EXTENSION
 CHESTER CREEK
 DRAINAGE EASEMENT
 HEADWALL
 CONCRETE CHANNEL



NOT TO SCALE
GEOTECH EVALUATION SITES
 TP = TEST PIT
 TH B = TEST HOLE BORE



BOX CULVERT/CONCRETE CHANNEL CALCULATIONS

Channel Report

Thorpe Box Culvert

Rectangular

Bottom Width (ft) = 28.40
Total Depth (ft) = 3.00


Invert Elev (ft) = 2009.15
Slope (%) = 0.50
N-Value = 0.040

Calculations

Compute by: Known Q
Known Q (cfs) = 64.00

Highlighted

Depth (ft) = 0.94
Q (cfs) = 64.00
Area (sqft) = 26.70
Velocity (ft/s) = 2.40
Wetted Perim (ft) = 30.28
Crit Depth, Yc (ft) = 0.55
Top Width (ft) = 28.40
EGL (ft) = 1.03



Channel Report

Open Channel

Rectangular

Bottom Width (ft) = 5.00
Total Depth (ft) = 3.50


Invert Elev (ft) = 2008.92
Slope (%) = 0.50
N-Value = 0.013

Calculations

Compute by: Known Q
Known Q (cfs) = 64.00


Highlighted

Depth (ft) = 1.61
Q (cfs) = 64.00
Area (sqft) = 8.05
Velocity (ft/s) = 7.95
Wetted Perim (ft) = 8.22
Crit Depth, Yc (ft) = 1.73
Top Width (ft) = 5.00
EGL (ft) = 2.59



PIPE SYSTEM CALCULATIONS

Hydraflow Storm Sewers Extension for Autodesk® AutoCAD® Civil 3D® Plan



FL-DOT Report

Line No	To Line	Type of struc	n - Value	Len (ft)	Drainage Area			Time of conc (min)	Time of Flow in sect (min)	Inten (l) (in/hr)	Total CA	Add Q Total Flow (cfs)	Inlet elev (ft)	Elev of HGL			Rise Span	HGL Pipe	ADD		Date: 10/13/2016					
					C1 = 0.2	C2 = 0.5	C3 = 0.9							Up (ft)	Down (ft)	Fall (ft)			Size (in)	Slope (%)		Vel (ft/s)	Cap (cfs)			
																								Incre- ment (ac)	Sub- Total (ac)	Sum CA
1	End	MH	0.013	95.291	0.00	0.00	0.00	10.55	0.39	0.00	0.00	2008.68	2004.73	2006.34	2001.34	60	0.16	5.62	79.00	Pipe - (1)						
2	1	MH	0.013	357.374	0.00	0.00	0.00	9.07	1.48	0.00	0.00	2012.87	2005.61	2006.70	2001.70	60	0.10	4.79	79.00	Pipe - (2)						
3	2	None	0.013	70.839	0.00	0.00	0.00	0.00	0.23	0.00	0.00	2005.87	2007.03	2007.37	2005.87	18	1.04	6.33	9.00	Pipe - (9)						
4	2	MH	0.013	600.822	0.00	0.00	0.00	6.26	2.81	0.00	0.00	2008.85	2006.37	2007.29	2002.29	60	0.07	4.00	70.00	Pipe - (3)						
5	4	None	0.013	71.843	0.00	0.00	0.00	0.00	2.12	0.00	0.00	2006.56	2008.93	2008.06	2006.56	18	0.42	1.95	1.00	Pipe - (10)						
6	4	MH	0.013	202.450	0.00	0.00	0.00	5.30	0.96	0.00	0.00	2008.95	2006.75	2007.49	2002.49	60	0.06	3.84	69.00	Pipe - (4)						
7	6	MH	0.013	197.451	0.00	0.00	0.00	4.37	0.94	0.00	0.00	2011.72	2006.91	2007.69	2002.69	60	0.06	3.87	69.00	Pipe - (5)						
8	7	None	0.013	71.291	0.00	0.00	0.00	0.00	2.10	0.00	0.00	2007.72	2008.09	2009.22	2007.72	18	1.33	1.88	1.00	Pipe - (11)						
9	7	MH	0.013	577.952	0.00	0.00	0.00	1.58	2.78	0.00	0.00	2011.00	2007.49	2008.25	2003.25	60	0.06	3.76	68.00	Pipe - (6)						
10	9	MH	0.013	146.439	0.00	0.00	0.00	0.88	0.70	0.00	0.00	2011.72	2006.18	2008.86	2003.86	60	-0.91	5.71	68.00	Pipe - (7)						

NOTES: Intensity = 127.16 / (Inlet time + 17.80) ^ 0.82 (in/hr) ; Time of flow in section is based on full flow.

Project File: Madison Pipe.stm


FL-DOT Report

Line No	To Line	Type of struc	n - Value	Len (ft)	Drainage Area			Time of conc (min)	Time of Flow in sect (min)	Inten (l) (in/hr)	Total CA	Add Q Total Flow (cfs)	Inlet elev (ft)	Elev of HGL			Rise Span	HGL Pipe	ADD Full Flow	Date: 10/13/2016 Frequency: 100 yrs Proj: Madison Pipe.stm								
					Incr-ment (ac)	Sub-Total (ac)	Sum CA							Up (ft)	Down (ft)	Fall (ft)					Size (in)	Slope (%)	Vel (ft/s)	Cap (cfs)	Line description			
																										0.2	0.5	0.9
11	10	None	0.013	69.575	0.00	0.00	0.00	0.00	0.51	0.00	0.00	2007.72	2008.50	2008.14	0.36	18	0.52	4.33	4.00	Pipe - (12)								
					0.00	0.00	0.00	0.00	0.00	0.00	2009.22	2008.86	0.36	18	0.52	4.27	7.55											
12	10	MH	0.013	268.775	0.00	0.00	0.00	0.00	0.88	0.00	0.00	2014.25	2009.46	2006.85	2.62	48	0.97	9.18	64.00	Pipe - (8)								
					0.00	0.00	0.00	0.00	0.00	0.00	2011.05	2008.86	48	0.81	10.32	129.7												
					0.00	0.00	0.00	0.00	0.00	0.00	2007.05	2004.86	2.19	Cir														


NOTES: Intensity = 127.16 / (Inlet time + 17.80) ^ 0.82 (in/hr) ; Time of flow in section is based on full flow.

Project File: Madison Pipe.stm


Storm Sewer Profile




Storm Sewer Profile




Storm Sewer Profile



Storm Sewer Profile



Storm Sewer Profile



GRAVEL GALLERY WORKSHEET - NORTH

WHIPPLE CONSULTING ENGINEERS

GRAVEL GALLERY CALC SHEET

10/13/2016

13-1166 Painted Hills PRD
ENGINEER BNG

Note: infiltration rates per IPEC Geotechnical Report Dated December 31, 2013

Gallery Depth (Min)	ft	Porosity of Gravel (Typ)	cf/cf	Infiltration Rate	cfs/sf
	13		0.3		1.80E-03

Gallery	Number of Galleries	Length	Width	Ground Water EL.	Gravel Gallery Bott. EL	Volume	Storage Volume	Perimeter	Sidewall Area	Bottom Area	Outflow
		ft	ft	ft	ft	cf	cf	ft	sf	sf	cfs
A	1	450.00	10.00	-	1000.00	58,500	17,550	920	11,960	4,500	29.63
B	1	450.00	10.00	-	1000.00	58,500	17,550	920	11,960	4,500	29.63
C	1	450.00	10.00	-	1000.00	58,500	17,550	920	11,960	4,500	29.63
D	1	450.00	10.00	-	1000.00	58,500	17,550	920	11,960	4,500	29.63
Totals	4	1800	10			234,000	70,200	3,680	23,920	9,000	118.51

Storage Volume = Volume* Porosity
Sidewall Area = Perimeter*Depth
Outflow = Sidewall Area + Bottom Area * Infiltration Rate

Note: Outflow Assumes a Full Gallery

BIO-INFILTRATION CHANNEL WORKSHEET

Bio-filtration Swale Design - Swale A3

Based on King County 2005 Surface Water Design Manual (Section 6.2 and 6.3)

Calculation of Design Flow:

$$Q_{wq} = 0.64 * (2\text{-yr peak flow rate})$$

$$Q_{\text{peak}, 2} = 79.00 \text{ cfs}$$

$$Q_{wq} = 50.56 \text{ cfs}$$

Calculation of swale bottom width:

$$Q = 1.49 A R^{0.67} S^{0.5} n^{-1} \quad \text{Manning's equation}$$

OR

$$b = Q_{wq} n_{wq} (1.49 * y^{1.67} S^{0.5})^{-1}$$

OR

$$y = [Q_{wq} n_{wq} (1.49 * b * S^{0.5})^{-1}]^{0.6}$$

width known:

$$b = 6.00 \text{ ft}$$

$$S = 0.010 \text{ ft/ft}$$

$$y = 4.29 \text{ ft}$$

where b = bottom width of swale (ft)...minimum 2 ft width required, maximum 10 ft

Q_{wq} = water quality design flow (cfs)

n_{wq} = Manning's roughness coefficient for shallow flow conditions = 0.20 (unitless)

y = design flow depth

S = longitudinal slope (along direction of flow) (ft/ft), slope shall be between 1%-6%. If less than 1.5%, underdrains must be provided. Slope less than 1% is considered a "wet biofiltration swale" and must be designed under those guidelines. Slope greater than 6% requires check dams with vertical drops of 12-inches

Determining design flow velocity:

$$V_{wq} = Q_{wq} / A_{wq}, \text{ max } 1.0 \text{ fps}$$

$$A_{wq} = b*y + Z*y^2$$

$$Z = 2$$

$$A_{wq} = 62.47 \text{ sf}$$

$$V_{wq} = 0.81 \text{ fps}$$

where V_{wq} = design flow velocity (fps)

A_{wq} = cross-sectional area of flow at design depth (sf)

Z = side slope length per unit height (e.g. for 3:1, $Z = 3$)

Calculate swale length to achieve a minimum hydraulic residence time of 9 minutes (540 seconds):

$$L = 540 * V_{wq}, \text{ minimum swale length is } 100 \text{ ft}$$


$$L = 437.07 \text{ ft}$$

Conveyance of larger storms using previous steps, Velocity must not exceed 3 fps:

$$Q_{\text{peak},25} = 2.5 \text{ cfs } y = 0.71 \text{ ft} \quad A_{25} = 5.23 \text{ sf} \quad V_{25} = 0.48$$

$$Q_{\text{peak},100} = 4.65 \text{ cfs } y = 1.02 \text{ ft} \quad A_{100} = 8.24 \text{ sf} \quad V_{100} = 0.56$$

MADISON RD CULVERT FLOWS



V-DITCH ROCK CALCULATIONS

Hydraulic Analysis Report

Project Data

Project Title: Triangle Pond **V-DITCH**

Designer:

Project Date: Monday, October 03, 2016

Project Units: U.S. Customary Units

Notes:

Channel Lining Analysis: Approach Channel Lining

Notes:

Lining Input Parameters

Channel Lining Type: Riprap, Cobble, or Gravel

D50: 1 ft

Riprap Specific Weight: 165 lb/ft³

Water Specific Weight: 62.4 lb/ft³

Riprap Shape is Angular

Safety Factor: 1

Calculated Safety Factor: 1.08369

Lining Results

Angle of Repose: 41.7 degrees

Relative Flow Depth: 1.13551

Manning's n method: Bathurst

Manning's n: 0.129511

Channel Bottom Shear Results

V*: 0.812111

Reynold's Number: 66730.6

Shield's Parameter: 0.0642078

shear stress on channel bottom: 1.27808 lb/ft²

Permissible shear stress for channel bottom: 6.58772 lb/ft²

channel bottom is stable

Stable D50: 0.210246 ft

Channel Side Shear Results

K1: 1

K2: 0.968982

Kb: 0

shear stress on side of channel: 1.27808 lb/ft²

Permissible shear stress for side of channel: 6.38338 lb/ft²

Stable Side D50: 0.216977 lb/ft²

side of channel is stable

Channel Lining Stability Results

the channel is stable

Channel Summary

Report for channel

Channel Analysis: Channel Analysis

Notes:

Input Parameters

Channel Type: Trapezoidal
Side Slope 1 (Z1): 6.0000 ft/ft
Side Slope 2 (Z2): 6.0000 ft/ft
Channel Width: 3.0000 ft
Longitudinal Slope: 0.0100 ft/ft
Manning's n: 0.1295
Lining Type: Rock Riprap - 300 mm (12-inch)
Depth: 2.0482 ft

Result Parameters

Flow: 38.7908 cfs
Area of Flow: 31.3156 ft²
Wetted Perimeter: 27.9176 ft
Hydraulic Radius: 1.1217 ft
Average Velocity: 1.2387 ft/s
Top Width: 27.5785 ft
Froude Number: 0.2049
Critical Depth: 0.9907 ft
Critical Velocity: 4.3774 ft/s
Critical Slope: 0.2950 ft/ft
Critical Top Width: 14.89 ft
Calculated Max Shear Stress: 1.2781 lb/ft²
Calculated Avg Shear Stress: 0.7000 lb/ft²

IPEC Geotechnical Report dated June 28, 2016
Full-Scale Drywell Testing

IPEC

Inland Pacific Engineering Company
Geotechnical Engineering and Consulting

June 28, 2016
Project No. 16-249A

NAI Black
c/o Mr. Bryan Walker
107 South Howard
Suite 500
Spokane, WA 99201

Re: **Full-Scale Drywell Testing**
Proposed Stormwater Management Facility
4403 South Dishman-Mica Road
Spokane Valley, WA

Dear Mr. Walker:

As you authorized, we have completed a full-scale drywell test on the drywell installed at the above-referenced site in Spokane Valley, Washington. The purpose of the testing was to establish a design flow rate. This report summarizes the results of our site investigation, engineering analyses and recommendations.

AVAILABLE INFORMATION

We were provided a topographic survey for the project site by Whipple Consulting Engineers, Inc. (WCE). This topographic survey showed the existing roadways, existing structures, property lines, and existing ground surface elevation contours. This plan was prepared by WCE and was dated November 7, 2013. The site was used as a golf course prior to our evaluation. The site is relatively level with some elevated golf greens and excavated areas for water hazards. The site is primarily grass-covered with scattered trees along the fairways and pine trees in the undeveloped area to the northwest. The clubhouse building is present at the southwest corner.

In addition, we performed a preliminary geotechnical evaluation for the property in December 2013. The results of that evaluation, along with our opinions and recommendations, are summarized in our Preliminary Geotechnical Evaluation dated December 31, 2013.

We also performed a geotechnical evaluation for certification of the existing levee along Chester Creek in April 2014. The results of that evaluation are summarized in our Geotechnical Evaluation report dated February 12, 2015.

Lastly, we performed a geotechnical evaluation in July 2015 consisting of ten 50-foot borings in the south half of the property. The results of that evaluation are summarized in our Geotechnical Evaluation Phase 2 report dated July 23, 2015.

FIELD EVALUATION

A geotechnical engineer from Inland Pacific Engineering Company (IPEC) performed a full-scale drywell test on the Type 2 drywell on May 6, 2016. The drywell test was performed in accordance with the Spokane Regional Stormwater Manual, Appendix 4B procedures.

ANALYSIS AND RECOMMENDATIONS

We calculated a design outflow rate for the existing drywell using the results of the recent and previous laboratory tests and the procedures described in the SRSM manual, Appendix 4B (Full-Scale Drywell Test Method). Based on the test performed, we recommend using a design flow rate of 1.05 cfs for design. This recommended design outflow rate includes a safety factor of 1.1 as required by the SRSM.

REMARKS

This report is for the exclusive use of the addressee and the copied parties to use in design of the proposed project and to prepare construction documents. In the absence of our written approval, we make no representations and assume no responsibility to other parties regarding this report. The data, analyses, and recommendations may not be appropriate for other structures or purposes. We recommend that parties contemplating other structures or purposes contact us.

Services performed by the geotechnical engineers for this project have been conducted in a manner consistent with that level of care ordinarily exercised by members of the profession currently practicing in this area under similar budget and time restraints. No warranty, expressed or implied, is intended or made.

GENERAL REMARKS

It has been a pleasure being of service to you for this project. If you have any questions or need additional information, please do not hesitate to call me at (509) 209-6262 at your convenience.

Sincerely,
Inland Pacific Engineering Company



Paul T. Nelson, P.E.
Principal Engineer

Attachments: Figure 1, Site Location Map
Figure 2, NRCS Map
Laboratory Test Results
Full-Scale Drywell Test Results





FIGURE 1



Site Location Map		
IPEC Inland Pacific Engineering Company Geotechnical Engineering and Consulting	Project No. 16-249A	June 28, 2016
	Painted Hills Golf Course 4403 South Dishman-Mica Road Spokane County, WA	

FIGURE 2



NRCS Map		
IPEC Inland Pacific Engineering Company Geotechnical Engineering and Consulting	Project No. 16-249A	June 28, 2016
	Painted Hills Golf Course 4403 South Dishman-Mica Road Spokane County, WA	



Inland Pacific Engineering Company
 3012 North Sullivan Road, Suite C
 Spokane Valley, WA 99216
 Telephone: 509-209-6262
 Fax: 509-290-5734


GRAIN SIZE DISTRIBUTION

CLIENT NAI Black

PROJECT NAME Painted Hills Drywell Test

PROJECT NUMBER 16-249A

PROJECT LOCATION 4403 South Dishman-Mica Road



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

BOREHOLE	DEPTH	Classification	LL	PL	PI	Cc	Cu
● L16-057	20.0	SP Poorly Graded Sand with Gravel				1.00	5.76

BOREHOLE	DEPTH	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
● L16-057	20.0	50	5.212	2.167	0.904	42.9	53.6	3.5	

GRAIN SIZE - GINT STD US LAB.GDT - 6/28/16 15:32 - J:\IPEC PROJECTS\16-249A PAINTED HILLS DRYWELL TESTING\GINT\16-249A PAINTED HILLS DRYWELL TEST.GPJ

IPEC

Inland Pacific Engineering Company
Geotechnical Engineering and Consulting

Full-Scale Drywell Test Results

Project Name: Painted Hills Drywell Test

Test Date: 5/6/2016

Project Number: 16-249A

Test Location: Existing Drywell

Client: NAI Black

Depth: 20'

Time	Elapsed Time (seconds)	Depth to Water (feet)	Flow Meter Reading (ft ³)	Volume of Water (ft ³)	Flow Rate (cfs)
10:00	0	19.5	596.6		
11:00	3600	18.2	1171.5	574.90	1.60E-01
11:10	600	18.2	1261.0	89.50	1.49E-01
11:20	600	18.2	1350.7	89.70	1.50E-01
11:30	600	18.2	1441.1	90.40	1.51E-01
11:35		18.3			
11:40		18.6			
11:45		19.1			
11:50		19.5			

Average Flow Rate: 1.50E-01

